



Roof Renewal

Project Brief:

Renew a leaking flat roof and installation of roof lights into slate roof

Project Details

Renew a leaking roof completely.

The existing flat roof and all its sub-bases were removed and the lower flat roof was insulated with set to fall slabs with asphalt top coat.

The tiled roof was renewed and double battened to bring the air cavity to the correct width it was connected to the asphalt deck with air vents allowing cross ventilation through the roof which has prevented the internal damp problems.

This was the best and most cost effective detail that could be designed following the installation of an incorrect detail by others.

Project Facts & Figures

Budget:	0
Timescale:	1 week
Overspend	£3,745

Clients Comments:

.....Just the job....no more damp.....